

**COUNTY OF VENTURA  
PUBLIC WORKS AGENCY**

Date: April 2, 2024

To: All Prospective Bidders

From: Dave Fleisch  
Assistant Director of Public Works

**Addendum No. 1**

Subject: **Project Name: El Rio Pedestrian Improvements**  
**Specification No. RD24-05 Project No. 50616**  
**State Project No. ATPSB1L-5952(208)**  
**Bids to be Opened: April 23, 2024 (NO CHANGE IN BID DATE)**

Make the following modifications to the bidding documents for subject project:

1. Replace all pages of the Bid Table with the attached pages 1 to 4.

Bidders are required to acknowledge any Addenda in Bonfire before submitting their bid.

Approved: \_\_\_\_\_

  
Dave Fleisch, Assistant Director

\_\_\_\_\_  
4/2/2024

Date Approved

## **BID TABLE**

Schedule of work and prices for: **EL RIO PEDESTRIAN IMPROVEMENTS**

Item No.	Units	Approx. Quantity	Item Description	Payment Reference	Unit-Price (In Figures)	Item Total (In Figures)
1	LS	1	Mobilization	7-3.4.2		
2	LS	1	Traffic Control & Construction Signing	1003-8		
3	LS	1	Water Pollution Prevention	1004-3		
4	LS	1	Trench Excavation & Backfill	1006-2		
5	LS	1	Bracing & Shoring	1007-2		
6	LF	312	Reinforced Concrete Pipe (18" RCP)	1008-5		
7	LF	118	Reinforced Concrete Pipe (24" RCP)	1008-5		
8	LF	68	Reinforced Concrete Pipe (30" RCP)	1008-5		
9	LF	540	Reinforced Concrete Pipe (36" RCP)	1008-5		
10	LF	62	Reinforced Concrete Pipe (54" RCP)	1008-5		
11	LF	324	Reinforced Concrete Pipe (66" RCP)	1008-5		
12	LS	1	Removal of Existing Manhole & RCP	1009-2		
13	LS	1	RCP Tie into Existing Manhole	1010-2		
14	EA	1	RCP Concrete Cover	1011-2		
15	CY	110	Slurry Cement Backfill	1012-2		
16	EA	2	Storm Drain Manhole (MH1, MH2)	1013-2		
17	EA	1	Storm Drain Manhole (MH4)	1013-2		
18	EA	7	Storm Drain Manhole (MH3, MH5, MH6, MH7, MH8, MH9, MH10)	1013-2		
19	EA	12	Curb Opening Catch Basin (CB1, CB2, CB3, CB4, CB7, CB8, CB9, CB10, CB11, CB12, CB13, CB14)	1014-2		
20	EA	1	Curb Opening Catch Basin (CB5)	1014-2		
21	EA	1	Curb Opening Catch Basin , CB6)	1014-2		

Item No.	Units	Approx. Quantity	Item Description	Payment Reference	Unit-Price (In Figures)	Item Total (In Figures)
22	LF	400	Local Depression at` Catch Basin	1015-2		
23	LS	1	Sidewalk & Pavement Widening Preparation	1016-2		
24	EA	1	Pepper Tree Removal (H=40', W=36")	1017-3		
25	EA	2	Cluster of Yucca Trees Removal (H=40', W=60")	1017-3		
26	EA	12	Palm Tree Removal (H > 50')	1017-3		
27	EA	1	Chinese Pistache Tree Removal (H=30', W=30")	1017-3		
28	EA	1	Cypress Tree Removal (H=25', W=18")	1017-3		
29	EA	1	Deciduous Tree Removal (H=25', W=18")	1017-3		
30	LF	450	Chain Link & Vinyl Fence Relocation	1018-3		
31	LF	50	Masonry Block with Chain Link Fence Relocation	1019-2		
32	EA	18	Slide Gate Elevation Adjustment	1020-3		
33	EA	15	Swing Gate Elevation Adjustment	1020-3		
34	EA	10	Access Gate Elevation Adjustment	1021-3		
35	LS	1	Irrigation Line Repair and/or Adjustment	1022-2		
36	LF	3,403	4" Curb & Gutter	1023-2		
37	LF	8,530	6" Curb & Gutter	1023-2		
38	LF	4,566	4" Curb & Gutter with Opening	1024-2		
39	LF	956	6" Curb & Gutter with Opening	1024-2		
40	LF	2,400	6" Curb	1025-2		
41	LF	675	8" Curb	1025-2		
42	EA	75	3" PVC Pipe Drain to Gutter	1026-2		
43	EA	70	3" PVC Pipe Drain to Trench	1027-2		
44	LF	365	PCC Dwarf Wall	1028-2		
45	LF	1,850	PCC Thickened Edge Sidewalk	1029-2		
46	SF	81,200	PCC Sidewalk & Walkway, 4" Thick	1030-2		

Item No.	Units	Approx. Quantity	Item Description	Payment Reference	Unit-Price (In Figures)	Item Total (In Figures)
47	SF	45940	PCC Driveway Approach, 6" Thick	1031-2		
48	SF	3300	AC Driveway Approach Tie-in	1032-2		
49	SF	4300	PMB Driveway Approach Tie-in	1033-2		
50	SF	530	Colored Concrete Driveway Tie-in	1034-3		
51	SF	500	Colored Stamped Concrete Driveway Tie-in	1035-3		
52	SF	405	Paver Driveway Approach Tie-in	1036-3		
53	SF	904	Brick Driveway Approach Tie-in	1037-3		
54	EA	20	Reinforced Concrete Steps	1038-2		
55	EA	3	Reinforced Concrete Steps with Hand Railing	1039-2		
56	EA	1	PCC Ramp (300 to 399 SF, 2 ADA Pads)	1040-2		
57	EA	8	PCC Ramp (500 to 599 SF, 2 ADA Pads)	1040-2		
58	EA	11	PCC Ramp (600 to 699 SF, 2 ADA Pads)	1040-2		
59	EA	8	PCC Ramp (700 to 799 SF, 2 ADA Pads)	1040-2		
60	EA	4	PCC Ramp (800 to 899 SF, 2 ADA Pads)	1040-2		
61	EA	5	PCC Ramp (900 to 999 SF, 2 ADA Pads)	1040-2		
62	EA	5	PCC Ramp (1000 to 1099 SF, 2 ADA Pads)	1040-2		
63	EA	1	PCC Ramp (100 to 199 SF, 1 ADA Pad)	1040-2		
64	EA	1	PCC Ramp (400 to 499 SF, 1 ADA Pad)	1040-2		
65	EA	1	PCC Ramp (600 to 699 SF, 1 ADA Pad)	1040-2		
66	EA	1	PCC Ramp (700 to 799 SF, 1 ADA Pad)	1040-2		
67	EA	1	PCC Ramp (1200 to 1299 SF, 1 ADA Pad)	1040-2		
68	EA	1	PCC Ramp (500 to 599 SF, 3 ADA Pads)	1040-2		
69	EA	1	Truncated Domes ADA Tile, 3' x 4'	1041-2		

Item No.	Units	Approx. Quantity	Item Description	Payment Reference	Unit-Price (In Figures)	Item Total (In Figures)
70	LF	157	PCC Cross Gutter, 6'-Wide	1042-2		
71	LF	110	Retaining Wall Type 6A, (H=3'-4")	1043-2		
72	LF	5,522	Infiltration Trench	1044-2		
73	SF	19,900	AC Pavement Micro-milling	1045-2		
74	TN	50	AC Pavement Leveling Course	1047-2		
75	TN	4,360	AC Pavement Widening & Repair, 6" Thick	1048-5		
76	TN	25	AC Miscellaneous Paving	1049-4		
77	SY	50,530	Type II Emulsion-Aggregate Slurry	1050-11		
78	SF	9,575	Ladder Type Crosswalk	1051-2		
79	LS	1	Pavement Delineation, Striping & Signs	1052-5		
80	EA	20	Temporary Cluster Box Unit Mailbox, in place	1053-2		
81	EA	20	Cluster Box Unit Mailbox Relocation, in place	1054-2		
82	EA	14	Roadside Mailbox, in place	1055-2		
83	EA	13	Rectangular Rapid Flashing Beacon (RRFB), in place	1056-5		
84	EA	4	RRFB Relocation, in place	1057-2		
85	EA	10	Traffic Signal Loop Detector Replacement	1058-2		
86	EA	5	Manhole Frame & Cover Adjustment	1059-2		
87	EA	12	Sewer Cleanout Cover Adjustment	1060-2		
			<b>Total Amount Bid</b>			

Bid Table is shown here for informational purposes.

Bid Table shall be filled out by Bidders using the Bonfire website. Bidders will access the Schedule of Work and Prices on the Bonfire website and input their Unit Prices.