COUNTY OF VENTURA
PUBLIC WORKS AGENCY

Date: September 25, 2024

To: All Prospective Bidders

From: Gregg Strakaluse
Director, Public Works Agency

Addendum No. 3

Subject: Project Name: SANTA CLARA RIVER LEVEE DOWNSTREAM OF UPRR (SCR-3) – PHASE 2
Specification No.: WP25-05
Project No.: 82045/82047
Bids to be Opened: October 3, 2024

Make the following modifications to the bidding documents for the subject project:

1. Replace Sheet 17, Sheet Pile General Notes, Waler Beam, and Anchor Details with attached Revised Sheet 17, Sheet Pile General Notes, Waler Beam, and Anchor Details.

2. Replace Sub-Section 1014-3 of the Specifications with the following language:

1014-3 <u>CONSTRUCTION METHODS</u>

The Contractor shall arrange for three ground anchors pre-production verification tests prior to beginning the installation of the ground anchors under Bid Item No. 19. The pre-production verification tests must pass the requirements of load tests under Section 46-2.01 D. If the pre-production verification tests do not pass, a revision to the original design will be required. The redesign shall be discussed with the design engineer and geotechnical engineer.

Acknowledgment of this addendum is required on the Bonfire website when submitting your bid. Failure to do so may result in the disqualification of your bid.

Approved: _____ 09/25/24
Gregg Strakaluse, Director Date Approved